



A NETWORK OF KINGDOM BUILDING SERVICES

## Sales Quote

building buildings. building lives.

## Bill To:

Village Meadows Baptist Church  
c/o R.H. Davis Development Inc  
Richard Davis 520-508-8054  
255 W Kayetan Dr  
Sierra Vista, AZ 85635

## Project:

## Quote Number:

## Issue Date:

C489IRS2

07/19/16

## Ship To:

Village Meadows Baptist Church  
c/o R.H. Davis Development, Inc.  
Richard Davis 520-508-8054  
(PROVIDE SHIPPING ADDRESS)  
Sierra Vista, AZ 85635

Quantity	U/M	Item Number	Description	Unit Price	Extended
836	EA	Item #	Irwin Stadium Seating		
		REFER	Irwin 91B Millenium Upholstered Back and Seat, Quiet Rise (Includes material, freight & installation) (Refer to vendor quote for a detailed description of the product and/or services quoted including manufacturer's terms & conditions)		
		Freight Allowed	Freight allowed to jobsite (1) destination point		
		Installation	Installation is Included		
		TAX-EXCLUDED	*TAX IS NOT INCLUDED AND MAY APPLY WITHOUT PROOF OF TAX EXEMPTION.		
		Plan Date	Quote provided per Architectural plan dated REV0, 6/08/16		
All prices valid for 30 days from issue date, unless otherwise noted on attached document.				Total:	\$

For Tax purposes please send a copy of your state tax exempt certificate with order.

Needed On Site: \_\_\_\_\_

\_\_\_\_\_  
Authorized Signature

\_\_\_\_\_  
Date

BGW ARCHITECTS II PC  
2909 WASHINGTON BLVD | OGDEN, UT 84401  
P: 801.409.1366 | F: 801.622.8142  
BGWSUPPLY.COM

Please acknowledge your acceptance of this order and BGW's General Terms, Conditions, and Allowances, by signing and returning by fax, mail, or email.



# Seating Proposal

*Valid for 90 Days*

**DATE:** Monday, July 18, 2016  
**QUOTE EXPIRES:** Sunday, October 16, 2016  
**TO:** Ernie Archulete  
Building God's Way  
**REFERENCE:** Village Meadows Baptist Church  
Sierra Vista, AZ

We are pleased to offer the following proposal for Irwin Seating model: 91•12•66•4

QTY	DESCRIPTION
836	91B Millennium - upholstered back with 2" poly and molded polyethylene outer.
836	12S Ergo - upholstered seat with ergonomic substrate and glass filled polypropylene seat structure. Seat fold - 3/4 Fabric: Sherpa or Shire 4C universal steel standard platform 66E Laminate End Panel Flat wood armrest. (Centers) Flat wood armrest. (Aisles)
836	Optional quiet rise seat lift.
836	Regular size (100) plywood core tablet arm writing surface, laminated on two sides.
8	ADA transfer arm.
25	Spare seat covers.
25	Spare back covers.
254	Worship Caddy II - envelope, pencil and / or communion cup holder. Hilti anchor Cover caps for anchor bolts. All wood to be Maple - Rotary Cut Irwin standard stain. Irwin standard powder coat. Irwin standard plastic on seat component. Irwin standard plastic on back component. Irwin standard laminate (Nevamar).
1	Freight Open Shop Installer to provide dumpster

## TERMS AND CONDITIONS

- Payment Terms are to be approved by Irwin Seating Company

### Unless otherwise noted:

- This proposal is subject to Irwin Seating Company Standard Terms and Conditions.
- This proposal is based upon the use of standard Irwin Seating Company products,

manufactured using standard Irwin Seating Company methods.

- This proposal is based upon the use of the referenced fabric, and standard paint, plastic, stain and laminate selections. Options or special details are only provided to the extent specifically listed in this proposal. If any of the above specifications change, alternative pricing must be quoted.
- Pricing is based on floor mount chairs mounted to concrete unless specified otherwise in this proposal.
- Pricing is based on minimum average row length of 10 chairs.
- Pricing is based on 54" wide fabric without a pattern or direction orientation specified. Railroaded (directional) fabrics or fabric with repeats may result in additional costs.
- Pricing is F.O.B. factory and does not include freight, installation, sales tax, and performance and payment bonds.
- If applicable, sales tax will be charged based on the tax rate in effect at the time of billing. For tax exempt orders, please provide Irwin Seating Company a copy of your tax exempt certificate along with your purchase order for review and approval.
- Pricing is based on shipment in the 2017 calendar year.
- Storage and order modification fees may be incurred if changes are requested after the order is entered into production.
- Adherence to project milestones as outlined in the critical date schedule is required to meet requested shipment dates.
- Our quotation is based upon the following concrete specifications: (if applicable)
  - 1) Floor mounted chairs must be 3" thick free from obstructions for top 1-1/2".
  - 2) Riser mounted chairs must be 4" thick free from obstructions for 2-1/2" from riser face.
  - 3) Riser to be plumb + or - 1/8".
  - 4) Normal weight concrete to be compressive strength 3000 PSI (structural concrete).
  - 5) Structural light weight concrete is acceptable if it is 2500 PSI minimum and weights 90-115 pounds per cubic foot.
  - 6) Screed is not an acceptable anchoring base. If screed dimension exceeds 1", special installation hardware and procedures may be necessary.

Any deviations from the concrete conditions mentioned above may result in additional installation charges, the need for alternative anchoring, etc. Installers need to be able to easily drill through the screed to reach clear structural concrete.

- Our quotation is based upon the following wood specifications: (if applicable)
  - 1) Minimum of 1-1/2" thickness
  - 2) Construction:
    - A. PLYWOOD: (Minimum Requirements)  
C-DX underlayment; Plug and touch sanding; Tongue and grooved
    - B. FLOORING: Sub floor plus hard wood (tongue and groove) finish flooring.
  - 3) Method of Fastening: No. 14X2" Hex washer head S.M. screw

NOTE: Wood construction for riser mounting is not recommended.

Any deviations from the conditions mentioned above may result in additional installation charges, the need for alternative anchoring, etc.

- Pricing is valid for 90 days from date of issue. If purchase order is not received within 90 days of this quote date Irwin Seating Company reserves the right to reissue the quotation with adjusted pricing.

If you have any questions, please contact your Irwin Seating Company Project Administrator for clarification.

IRWIN SEATING COMPANY

Jeni Lindhout  
Project Coordinator



A NETWORK OF KINGDOM BUILDING SERVICES

## Sales Quote

building buildings. building lives.

## Bill To:

Village Meadows Baptist Church  
c/o R.H. Davis Development Inc  
Richard Davis 520-508-8054  
255 W Kayetan Dr  
Sierra Vista, AZ 85635

## Project:

## Quote Number:

## Issue Date:

C489PF1

07/19/16

## Ship To:

Village Meadows Baptist Church  
c/o R.H. Davis Development Inc  
Richard Davis 520-508-8054  
(PROVIDE SHIP-TO ADDRESS)  
Sierra Vista, AZ 85635

Quantity	U/M	Item Number	Description	Unit Price	Extended
1	EA	Quote # REFER	PREFOAM / Stadium Seating Riser System Per Quote PREFOAM, Dated 5/13/2016 (Refer to vendor quote for a detailed description of the product and/or services quoted including manufacturer's terms & conditions)		
1	EA	Item # Prod, Desc, Quantity  Notes	Hot Wire Cutter Product, Description and Quantity may change due to Engineering review and approval, and may affect overall price **Quote Excludes** -Structural Engineering services including but not limited to structural design documents or calculations; -System Installation; -Any and all Client directed changes; -Adhesive or Gripper Plates for the installation of the EPS blocks; -Self-Tapping Screws for the installation of the steel forms; -Fire-rated gyp/cement board;		
All prices valid for 30 days from issue date, unless otherwise noted on attached document.				Total:	

For Tax purposes please send a copy of your state tax exempt certificate with order.

Needed On Site: \_\_\_\_\_

Authorized Signature

Date

BGW ARCHITECTS II PC  
2909 WASHINGTON BLVD | OGDEN, UT 84401  
P: 801.409.1366 | F: 801.622.8142  
BGWSUPPLY.COM

Please acknowledge your acceptance of this order and BGW's General Terms, Conditions, and Allowances, by signing and returning by fax, mail, or email.



A NETWORK OF KINGDOM BUILDING SERVICES

## Sales Quote

building buildings. building lives.

## Bill To:

Village Meadows Baptist Church  
c/o R.H. Davis Development Inc  
Richard Davis 520-508-8054  
255 W Kayetan Dr  
Sierra Vista, AZ 85635

## Project:

## Quote Number:

## Issue Date:

C489PF1

07/19/16

## Ship To:

Village Meadows Baptist Church  
c/o R.H. Davis Development Inc  
Richard Davis 520-508-8054  
(PROVIDE SHIP-TO ADDRESS)  
Sierra Vista, AZ 85635

Quantity	U/M	Item Number	Description	Unit Price	Extended
		Tax	-Concrete & reinforcing; -Steel riser plate for ramp edging; -Outside accounting servicing fees; -Any additional tax or fees. ***BGW Architects II PC / Supply is not registered to collect sales tax in your state. Payment of any such tax is the responsibility of the purchaser.***		0.00
		Plan Date	Quote provided per Architectural plan dated 2/8/2016		0.00
				0.00	0.00
All prices valid for 30 days from issue date, unless otherwise noted on attached document.				Total:	\$

For Tax purposes please send a copy of your state tax exempt certificate with order.

Needed On Site: \_\_\_\_\_

Authorized Signature

Date

BGW ARCHITECTS II PC  
2909 WASHINGTON BLVD | OGDEN, UT 84401  
P: 801.409.1366 | F: 801.622.8142  
BGWSUPPLY.COM

Please acknowledge your acceptance of this order and BGW's General Terms, Conditions, and Allowances, by signing and returning by fax, mail, or email.



Stadium Seating Enterprises, Inc.  
28202 Cabot Road, Suite 300  
Laguna Niguel, CA 92677  
Telephone: 949.363.7128  
Fax: 949.363.0837  
Web: [www.stadiumseating.com](http://www.stadiumseating.com)

**SSE PREFOAM™ STADIUM SEATING RISER SYSTEM PRELIMINARY QUOTATION**  
**DESIGN & FABRICATION - MATERIAL ONLY - FOB JOBSITE**

May 13, 2016

Ernie Archuleta  
Project Administrator  
**BGW Architects**  
2909 Washington Boulevard  
Ogden, UT 84401  
[earchuleta@bgwservices.com](mailto:earchuleta@bgwservices.com)

**REVISED TO REFLECT NEW DESIGN DATED 2/8/2016**

**Project: Village Meadows Baptist Church, Sierra Vista, AZ**

Dear Ernie,

Stadium Seating Enterprises, Inc. is pleased to provide **BGW Architects** with this quotation for the SSE **PREFoam™** Stadium Seating Riser System for the **Village Meadows Baptist Church** project.

SSE Quotation	
Base Bid	
Bid Alternate – Hot Wire Cutter	
Bid Qualifications	
Material Sales Tax	If appropriate, tax will be added to contract amount at time of execution or client shall provide tax exempt certificate.
Bid Based on Plans Dated	2/8/2016
Project Information	
Number of Sectors	Four
EPS Type	EPS 15

**This preliminary quotation is based on the current price of materials and freight. All costs will be recalculated at the time the final construction documents are complete and a firm date for delivery of the system to the jobsite is established.**

**SSE STADIUM SEATING SYSTEM QUOTATION**

*All information contained within this quotation is confidential. This information is for the use of the intended receiver only and any distribution of this information without permission of SSE is strictly prohibited.*

**Village Meadows Quote dated May 13, 2016**



Stadium Seating Enterprises, Inc.  
28202 Cabot Road, Suite 300  
Laguna Niguel, CA 92677  
Telephone: 949.363.7128  
Fax: 949.363.0837  
Web: [www.stadiumseating.com](http://www.stadiumseating.com)

**Quote Includes:**

- Electronic shop drawings detailing each auditorium and each level of the tiered seating. All Major Components will be marked;
- EPS 15 Geofoam blocks;
- 16 GA steel riser plate precut to the dimension of each row of the platform and ready for primer and painting by others (*Risers come in 10' straight Sector. Contractor responsible for scoring riser flanges to achieve predesigned radius.*);
- 16 GA steel connecting hardware;
- 16 GA intermediate step forms ready for primer and painting by others;
- Shipping of the EPS Geofoam and Steel Components to the jobsite.

**Quote Excludes:**

- Structural Engineering services including but not limited to structural design documents or calculations;
- System Installation;
- Any and all Client directed changes;
- Adhesive or Gripper Plates for the installation of the EPS blocks;
- Self-Tapping Screws for the installation of the steel forms;
- Fire-rated gyp/cement board;
- Concrete & reinforcing;
- Steel riser plate for ramp edging;
- Outside accounting servicing fees;
- Any additional tax or fees.

**SSE STADIUM SEATING SYSTEM QUOTATION**

*All information contained within this quotation is confidential. This information is for the use of the intended receiver only and any distribution of this information without permission of SSE is strictly prohibited.*

**Village Meadows Quote dated May 13, 2016**

Page 2 of 3





Stadium Seating Enterprises, Inc.  
28202 Cabot Road, Suite 300  
Laguna Niguel, CA 92677  
Telephone: 949.363.7128  
Fax: 949.363.0837  
Web: [www.stadiumseating.com](http://www.stadiumseating.com)

## **GENERAL TERMS AND CONDITIONS**

This quotation is based on drawings provided by **BGW Architects** on **2/8/2016**. Any deviations from those plans resulting from differing field conditions, design changes or design documents not in the possession of SSE or referenced in this document are not the responsibility of SSE and not included in this quote.

SSE will provide electronic shop drawings based on the final approved drawings furnished to SSE by the Client/GC/Architect of Record. Shop drawing design changes that require extensive revisions are not included in the basic services and are considered an additional billable service. SSE shop/installation drawings are not stamped by an architect/engineer and are not intended to be submitted to the local building department for approval. All issues related to building code, structural design/calculations, seismic restraint, exiting, fire and life safety, ADA compliance, etc. are the responsibility of the Architect/Engineer of Record.

In the case of renovation projects, SSE shall be provided with field verified floor elevations. All voids caused by uneven existing floor conditions shall be filled to allow EPS block to have full bearing capacity on the existing slab. In the case of existing slabs where the slab has differing elevations across the width of the slab, the contractor shall fill in dips or imperfections with leveling material leaving a finished surface that has a single slope from front to back. SSE shall not be responsible to cut the EPS block with a compound slope to achieve full bearing capacity.

SSE's services will be performed in a timely manner consistent with good professional practices. Client acknowledges that SSE is not responsible for the performance of others and in no event will SSE have any responsibility for any errors, omissions or delays caused by others.

Thank you for the opportunity to provide you with this quotation for the SSE **PREFoam** Stadium Seating Riser System for the **Village Meadows Baptist Church** project.

We look forward to the opportunity of working with you to complete your project.

Sincerely,

A handwritten signature in black ink, appearing to read 'T. Moson', written over a horizontal line.

Taylor B. Moson, President

**Accepted:**

---

**By:**

**Date:**

### ***SSE STADIUM SEATING SYSTEM QUOTATION***

*All information contained within this quotation is confidential. This information is for the use of the intended receiver only and any distribution of this information without permission of SSE is strictly prohibited.*

**Village Meadows Quote dated May 13, 2016**